

15-135-22276-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY NESS SEC. 28 TWP. 16S RGE. 21W E/W  
Location as in quarters or footage from lines:  
S/2 S/2 SE/4 SEC.


Lease Owner Chief Drilling Co., Inc.  
Lease Name Stephens Well No. #1 "A"  
Office Address 905 Century Plaza Wichita, Ks. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 8-17-82  
Application for plugging filed 8-17-82  
Plugging commenced 8-17-82  
Plugging completed 8-17-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4235

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface Casing	7 jts. new			8 5/8"	280 1/2' set	@ 283'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugging w/70 sx. @ 960', 40 sx. @ 300',  
10 sx. @ 40', 10 sx. in Rathole, 130 sx.  
total, 50-50 posmix, 4% gel, 3% c.c. Started  
@ 6:00 p.m. Finished @ 7:15 p.m. Steve Durrant Belpree  
State Plugger

RECEIVED  
STATE CORPORATION COMMISSION

AUG 20 1982

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Warrior Drilling Co.  
905 Century Plaza Wichita, Ks. 67202

CONSERVATION DIVISION  
Wichita Kansas

STATE OF Kansas COUNTY OF Ness, ss.

F.W. Shelton, Jr., Vice President (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.  
F.W. Shelton, Jr., Vice President  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1982

MARtha E. GUSTIN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 4-15-85

Martha E. Gustin  
Martha E. Gustin  
Notary Public.

My Commission expires:

WELL LOG

15-135-22276-00-00

CHIEF DRILLING CO., INC.  
905 Century Plaza  
Wichita, Kansas 67202

#1 "A" STEPHENS  
S/2 S/2 SE/4 28-16S-21W  
NESS COUNTY, KANSAS

CONTRACTOR: Warrior Drilling Co. COMMENCED: 8-9-82  
CASING RECORD: Ran 7 jts. new 20# 8 5/8" 280 1/2' set COMPLETED: 8-17-82  
@ 283' Gr. cemented w/150 sx. common, 6% gel,  
3% c.c., started @ 10:20 p.m. Completed @ 10:45 p.m.

FORMATION	FROM	TO	ELEVATIONS
Surface Sand & Clay	0	292	2257 GR.
Clay & Sand	292	335	2259 D.F.
Sand & Shale	335	1020	2262 K.B.
Shale & Sand	1020	1552	
Anhydrite	1552	1581	
Shale	1581	1910	
Shale & Lime	1910	2290	
Shale	2290	3277	
Lime & Shale	3277	3665	
Shale & Lime	3665	3823	
Lime	3823	4235	
RTD	4235		

D & A

RECEIVED  
STATE CORPORATION COMMISSION

AUG 20 1982

CONSERVATION DIVISION  
Wichita, Kansas

08-20-1982

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the S/2 S/2 SE/4 Sec. 28-16-21W Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*F. W. Shelton, Jr.*

F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this 18th day of August 1982.

MARSHA E. GUSTIN  
Notary Public

Martha E. Gustin