

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-135-23778-00-00

LEASE NAME Hiltabidle

TYPE OR PRINT

NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER "A" #3

4306 Ft. from S Section Line

3200 Ft. from E Section Line

SEC. 28 TWP. 16S RGE. 21W (E) or (W)

COUNTY Ness

LEASE OPERATOR American Energies Corporation

ADDRESS 155 North Market, Suite 710

Wichita, KS 67202

PHONE# (316) 263-5785 OPERATORS LICENSE NO. 5399

Date Well Completed 9/23/93

Character of Well \_\_\_\_\_

Plugging Commenced 9/23/93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/23/93

The plugging proposal was approved on 9/23/93 - Plug down at 10:15 p.m. (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Cherokee Depth to Top 4176 Bottom 4270 T.D. LTD: 4294

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing	Limestone Water	3728	4010	8 5/8"	254'	0
Cherokee	Shales Sand Water	4176	4270			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
1st Plug @ 1620' w/50 sx, 2nd Plug @ 920' w/80 sx, 3rd Plug @ 475' w/40 sx,  
4th Plug @ 270' w/50 sx, 5th Plug @ 40' w/10 sx, Rathole w/15 sx,  
Mousehole w/10 sx - Total of 255 sx 60/40 poz (6% gel), 14# floseal per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. None Required

Address North Hwy 281, P.O. Box 628, Great Bend, Kansas 67530-0628

STATE OF Kansas COUNTY Sedgwick, ss.

Alan L. DeGood, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the logging of the above-described well as filed that the same are true and correct, so help me God.

09-30-1993

(Signature) Alan L. DeGood  
 Alan L. DeGood, Vice-President  
 American Energies Corp.

(Address) 155 N. Market, Suite 710, Wichita KS

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1993

Melinda S. Wooten  
 Notary Public  
 Melinda S. Wooten

My Commission Expires: 3-12-96

