

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,601-00-00

LEASE NAME Hinman

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

4060 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 27 TWP. 16 RGE. 21 (E) or (W)

COUNTY Ness

Date Well Completed 09-14-91

Plugging Commenced 09-14-91

Plugging Completed 09-15-91

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS P.O. Box 47 Great Bend, KS 67530

PHONE# (316) 793-5100 OPERATORS LICENSE NO. 6569

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-12-91 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
						SEP 18 1991
						09-18-1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1630' w/50 sacks cement thru drill pipe 15 sacks in Rat Hole

Next Plug: @ 1050' w/80 " " " " "

Next Plug: @ 450' w/60 " " " " "

Top Plug: @ 40' w/10 " " " " "

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929-

Address P.O. Box 823 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Jay Schneider

(Employee of Operator) or ~~(Operator)~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 91

Paula Ann Laddick
Notary Public

My Commission Expires: _____



DRILLER'S WELL LOG

DATE COMMENCED: September 8, 1991
DATE COMPLETED: September 15, 1991

Carmen Schmitt, Inc.
#1 HINMAN
100'N of NW/4
Sec. 27, T16S, R21W
Ness County, Ks.

0 - 1087' Surface Soil, Clay, Shale, Sand
1087 - 1573' Lime & Shale
1573 - 1608' Anhydrite
1608 - 4152' Lime & Shale
4152 - 4162' Sand
4162 - 4192' Lime, Shale, Sand
4192 - 4250' Lime & Shale
4250' RTD

ELEVATION: 2286' K.B.

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1991


Surface Pipe: Set used
8-5/8", 20# pipe @ 216'
w/140 sacks 60/40 pozmix
25 gel 3% cc.


A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Jay Schneider of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Subscribed and sworn to before me this 17 day of September 1991.




Notary Public