

15-135-20096-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 27 Twp. 6S Rge. (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines C NW SW
Lease Owner Chief Drilling Co., Inc.
Lease Name Stephens Well No. 1
Office Address Box 797 - Gt. Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 12/21 1967
Application for plugging filed 12/20 1967
Application for plugging approved 12/20 1967
Plugging commenced 12/20 1967
Plugging completed 12/21 1967
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey - Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4235 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	269'	8-5/8"	269'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped through drill pipe with pump truck
100 sacks cement @ 720'
25 sacks cement @ 240'
10 sacks cement @ 40'
Used Allied Cementing Co., Inc. 50/50 Pozmix, 6% Gel.

DEC 22 1967
12-22-1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Gt. Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Thomas Wesselowski (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. CHIEF DRILLING CO., INC.

(Signature) Thomas Wesselowski
Box 797 - Gt. Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 21st day of December, 1967
Carmen R. Cook
Carmen R. Cook, Notary Public.



15-135-20096-00-00

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1967

12-22-1967

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas 67530

STEPHENS #1
C NW SW Sec. 27-16S-21W
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 12-11-67
Completed: 12-21-67

Casing Record: 8-5/8" set @ 269' w/175 sacks Quickset cement


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>	
			2256 Gr.	
			2258 D.F.	
			2261 K.B.	
			<u>FORMATION TOPS</u>	
			<u>SAMPLE</u>	<u>LOG</u>
Surface Clay	0	40	Heebner	3645 3643 -1382
Shale & Sand Streaks	40	268	Toronto	3665 3664 -1403
Shale, Sand Streaks & Red Bed	268	645	Lansing	3686 3685 -1424
Shale & Shells	645	980	Base Kansas City	3971 3970 -1709
Sand	980	1220	Pawnee	4039 4040 -1779
Shale & Shells	1220	1300	Ft. Scott	4131 4131 -1870
Shale, Shells & Sand Streaks	1300	1549	Cherokee Shale	4136 4138 -1877
Anhydrite	1549	1587	Cherokee Sand	4139 4140 -1879
Shale & Shells	1587	2170	Mississippi	4202 4203 -1942
Shale & Lime	2170	2660	Total Depth	4235 4234 -1973
Lime	2660	2761		
Lime & Shale	2761	3712		
Lime	3712	3970		
Shale & Cherty Lime	3970	4040		
Cherty Lime	4040	4112		
Shale & Lime	4112	4138		
Sand & Shale	4138	4203		
Chert	4203	4235		
Total Depth	4235			

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C NW SW Section 27-16S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Thomas Wesselowski
Thomas Wesselowski, Geologist



Subscribed and sworn to before me this 21st day of December, 1967.

Carmen R. Cook
Carmen R. Cook, Notary Public

My Commission expires: Dec. 12, 1970