

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,714-00-00

LEASE NAME Baus

WELL NUMBER #1

SPOT LOCATION W 1/2 NE SW

SEC. 24 TWP 16S RGE. 21W (E) or (W)

COUNTY Ness

Date Well Completed 11-24-84

Plugging Commenced 11-24-84

Plugging Completed 11-24-84

LEASE OPERATOR The Reach Group

ADDRESS 3751 East Douglas, Wichita, Kansas 67218

PHONE # (316) 683-3626 OPERATORS LICENSE NO. 8572

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? _____

Which KCC/KDHE Joint Office did you notify? KCC, Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8-5/8"	300.20'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 1st plug @ 1500' w/50 sxs 60/40 pozmix (2% gel, 3% CaCl); 2nd plug @ 750' w/50 sxs; 3rd plug @ 360' w/40 sxs; 4th plug @ 40' w/10 sxs and solid bridge and 15 sxs in the rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Robert-Gay Energy Enterprises, Inc. License No. 8059

Address 1006 N. Main, Hutchinson, Kansas 67501

STATE OF KANSAS COUNTY OF RENO, ss. **RECEIVED**

STATE CORPORATION COMMISSION

Robert L. Taylor (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

JAN 03 1985
01-03-1985
CONSERVATION DIVISION
Wichita, Kansas

X (Signature) [Signature]
(Address) Robert L. Taylor
1006 North Main

Hutchinson, Ks 67501

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1984

Cheryl A Chance
Notary Public

My Commission expires: 6-6-87

15-135-22714-00-00

December 10, 1984

RE: The Reach Group #1 Baus
W $\frac{1}{2}$ NE SW
Section 24-T16S-R21W
Ness County, Kansas

OPERATOR: The Reach Group
CONTRACTOR: Robert-Gay Energy Enterprises, Inc.
DRILLING DATES: November 16, 1984 to November 24, 1984

Surface pipe set at 300.20' KB w/200 sacks common cement (2% gel, 3% CaCl).

0	1494	Sand & Shale
1494	1532	Anhydrite
1532	3654	Lime & Shale
3654	3917	Lansing
3917	4062	Lime & Shale
4062	4130	Sand & Shale
4130	4165	Mississippian

RTD 4165'

We certify that the above and foregoing is a true and correct copy of the log on The Reach Group #1 Baus in Ness County, Kansas

ROBERT-GAY ENERGY ENTERPRISES, INC. RECEIVED
STATE CORPORATION COMMISSION

Robert L. Taylor, President

JAN 03 1985

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 12th day of December, 1984.

My commission expires:



Cheryl A. Chance Notary Public