

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23, 106-0000

LEASE NAME Skaggs

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 23 TWP. 16 RGE. 21 051X(W)

LEASE OPERATOR Hess Oil Company

ADDRESS P. O. Box 1009

COUNTY Ness

PHONE# (316) 241-4640 OPERATORS LICENSE NO. 5663

Date Well Completed 5/22/87

Character of Well D & A

Plugging Commenced 5/22/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5/22/87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4210'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation surface	Content	From	To	Size	Put In	Pulled out
		0'	230'	8 5/8"	230'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Plugged hole with 200 sacks 60/40 poz mix, 6% gel as follows:

50 sacks @ 1551'; 70 sacks @ 1197'; 40 sacks @ 260';

10 sacks @ 40'; 15 sacks rathole; 10 sacks mousehole;

P.D. @ 6:30 a.m. 5/22/87

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009 McPherson KS 67460


STATE OF Kansas COUNTY OF McPherson, ss.

Bryan Hess (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Hess

(Address) P. O. Box 1009, McPherson KS

SUBSCRIBED AND SWORN TO before me this 5th day of June, 1987



My Commission Expires: 11-15-89 STATE CORPORATION COMMISSION

RECEIVED Notary Public

JUN 11 1987  
06-11-1987  
CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 08-84

15-135-23106-00-00

DRILLERS' LOG

COMPANY: Hess Oil Company WELL: Skaggs #1  
 CONTRACTOR: Mallard Drilling API#: 15-135-23, 106  
 P. O. Box 1009 LOCATION: N2 NE SE  
 McPherson KS. 67460  
 COMMENCED: May 14, 1987 Sec. 23, Twp. 16S, Rge. 21W  
 COMPLETED: May 22, 1987 COUNTY: Ness  
 TOTAL DEPTH: 4210' ELEVATION: 2234' G. L.  
2242' K. B.

\*\*\*\*\*

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Soil, Shale	0'	969'
Sand	969'	1513'
Anhydrite	1513'	1536'
Shale	1536'	3194'
Shale, Lime	3194'	3933'
Lansing, Pawnee	3933'	4072'
Lime	4072'	4210'

R.T.D. Miss-Osage

REMARKS:

Cut 12 1/2" hole to 235' and ran 5 joints new 8 5/8" X 20# X 220.95' surface casing. Set at 230.45' and cemented with 150 sacks 60/40 poz mix, 3% cc, 2% gel. Cement did circulate. P.D. @ 5:25 a.m. on 5/16/87.

Ran electric log and 1 DST.

Plugged hole with 200 sacks 60/40 poz mix, 6% gel as follows:

- 50 sacks @ 1551'
- 70 sacks @ 1197'
- 40 sacks @ 260'
- 10 sacks @ 40'
- 15 sacks rathole
- 10 sacks mousehole

P.D. @ 6:30 a.m. 5/22/87.


\*\*\*\*\*

STATE OF KANSAS )  
 ) SS:  
 COUNTY OF McPHERSON)

I, BRYAN HESS of MALLARD DRILLING, do hereby certify that this is a true and correct copy of the log of the Skaggs #1 well as reflected by the files of Mallard Drilling.

*Bryan Hess*  
 Bryan Hess, Gen. Mgr.

Subscribed and sworn to before me this 5th day of June, 1987.



*Don J. Reichenberger*  
 Notary Public  
 RECEIVED  
 STATE CORPORATION COMMISSION

JUN 11 1987  
 06-11-1987  
 CONSERVATION DIVISION  
 Wichita, Kansas