

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,404-00-00

LEASE NAME Wyman

WELL NUMBER 2

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 19 TWP. 16S RGE. 21 ~~W~~ (W)

COUNTY Ness

Date Well Completed 11-20-89

Plugging Commenced 11-20-89

Plugging Completed 11-21-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Bankoff Oil Company

ADDRESS 100 S. Market, Suite 203A, Wichita, KS 67202

PHONE#(316) 262-2784 OPERATORS LICENSE NO. 6040

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-21-89 (date)

by State Plugger, Mike Spain (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4379'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	281.25'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circulate heavy mud 20 minutes. 1st plug from 1650' to 1450' w/50 sx. 2nd plug from 925' to 605' w/80 sx. 3rd plug from 310' to 150' w/40 sx. 4th plug from 40' SB to surface w/10 sx. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bankoff Oil Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 14th day of December, 19 89

Sharan J. Branstetter  
Sharan J. Branstetter Notary Public  
Commission Expires: May 18, 1993

