

15-101-20020-00-00

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling, Inc., & Petroleum Resources, Inc.,

Complete Address P. O. Box #18407, Wichita, Kansas.

Lease Name Fink Well No. 1

Location NW-SW-NW Sec. 24 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4696'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks. License No. \_\_\_\_\_

Operation Completed: Hour 9:45 AM Day 11E Month 10 Year 1971

The above well was plugged as follows:

283'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru  
DP from 1025' to 700'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from  
310' to 235', Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 10-13-71

INV. NO. 4475-W