

15-101-20021-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1973  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Thunderbird Drilling Company,  
Complete Address Box #18407, Wichita, Kansas.  
Lease Name Fink Well No. C-1  
Location SW-NE-NE Sec. 24 Twp. 16 Rge. (E) (W) 27  
County Lane Total Depth 4567'  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Kelso Casing Pulling,  
Address Box #176, Chase, Kansas. License No. 683  
Operation Completed: Hour 1:30 PM Day 21 Month 2 Year 1973

The above well was plugged as follows:

296'--8 5/8" Surface casing, cement circulated with---  
4557'--5 1/2" Production casing cemented on bottom with 250 Sx. No plug back indicated.  
Top of perforations @ 4035'.  
Pushed plug to 4000', sanded back from 4000' to 3975' and set 5 Sx. cement with dump  
bailer. Pulled 5 1/2" casing (1600') and squeezed well initially with 5 sacks hulls and  
15 sacks gel and followed with 110 Cu. Ft. cement from 1000' to 675' then 10 sacks gel  
from 675' to 300' and followed with 30 Cu. Ft. cement from 300' to 225' then 5 sacks  
gel from 225' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar.  
Maximum pump-in press.--500#. FSIP-300#. (Mudding, and cementing by Allied Cmtg., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 2/28/73  
INV. NO. 7049-W