

15-101-20048-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Rains and Williamson Oil Company, Incorporated,  
Complete Address 435 Page Court, 220 West Douglas, Wichita, Kansas.  
Lease Name Bentley Well No. 1  
Location SE-SE-NW Sec. 17 Twp. 16 Rge. (E) (W) 27  
County Lane Total Depth 4650'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Above  
Address \_\_\_\_\_ License No. \_\_\_\_\_  
Operation Completed: Hour 11:00 AM Day 11 Month 3 Year 1973

The above well was plugged as follows:

311'--8 5/8" Surface casing, cement circulated with 190 Sx.  
Top of Dakota section @ 775'.  
Circulated hole with heavy mud. Pulled DP to 1000' and displaced 110 Cu. Ft. cement  
thru DP from 1000' to 675'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols  
Well Plugging Supervisor

INVOICED

DATE 3/13/73  
INV. NO. 9120-w