

15-101-30004-00-00

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT**RECEIVED**
STATE CORPORATION COMMISSIONJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

AUG 10 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sioux Petroleum,

Complete Address: Dighton, Kansas.

Lease Name Broughton Well No. 3

Location NE SW CSW NE JD KCC Sec. 15 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4185

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: 815 Wichita Plaza, Wichita, Kansas. License No.

Operation Completed: Hour 5:30AM Day 7 Month 8 Year 1965

The Above well was plugged as follows:

106'--8 5/8" Surface pipe, cement circulated with 125 Sx.Circulated hole with heavy mud, set plug @ 600' and displaced 15 Sx.cement thru DP. Heavy mud to 120', set plug with 1/4 sack hulls and dis-
placed 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICEDSigned: N. L. Finkel

Well Plugging Supervisor

DATE 8/10/65INV. NO. 1603-W