

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-101-20, 645-00-06

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name AGIP PETROLEUM, INC.

Complete Address BOX 1409 GREAT BEND, KANS. 67530

Lease Name BROUGHTON Well No. F #1

Location C-NE-NE NWSE Sec. 15 Twp. 16 Rge. 27 (East)(West)

County LANE JDKCC Total Depth 4625 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor SLAWSON DRILLING CO. (RIG. 1) (RON ROWE)

Address 200 DOUGLAS BLDG. BROADWAY + DOUGLAS, WICHITA, KS License No. \_\_\_\_\_

Operation Completed: Hour: 8:30 PM Day: 20 Month: MARCH Year: 19 8182

Plugging Operations attended by Agent?: All  Part  None  JDKCC

The above well was plugged as follows:

8 5/8" - 328 FE SB. CUM. w/ 225 ST 60/40 Pozmix - 2% GEL - 3% CA-CL. (HALLIBURTON) <sup>BY</sup>

ORDERED 130 ST 50/50 Pozmix 4% GEL - 3% CA-CL. + 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1 ST PLUG @ 1080 FE w/ 70 ST CMT.

2 ND PLUG @ 300 FE w/ 40 ST CMT.

3 RD PLUG - SOLID BRIDGE HULLS PLUG @ 40 FE TO w/ 10 ST CMT.

10 ST IN RAT HOLE (CIRCUMISE)

CEMENTED BY HALLIBURTON CMT.

Amount of Surface Casing: 328 FE

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Marion Schmidt  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I GAVE ORAL PLUGGING ORDERS FOR CLARENCE THOMAS.  
SINCE HE IS ON SICK LEAVE.

RECEIVED  
STATE CORPORATION COMMISSION

Signed: Marion Schmidt  
Conservation Division Agent

MAR 30 1982  
CONSERVATION DIVISION  
Wichita Kansas

INVOICED

DATE 4-7-82  
TJV. NO. 9886-W