

15-135-20106-00-00

Form CP-3  
Rev. 6-9-67

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

JAN 1 1 1968

CONSERVATION DIVISION  
Wichita, Kansas

01-11-1968

Operator's Full Name O. A. Sutton

Complete Address 800 Sutton Place Wichita, Kansas

Lease Name Ryan Well No. 1

Location C SE SE Sec. 16 Twp. 16 Rge. 21 (E)  (W)

County Ness Total Depth 4310'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Gabbert-Jones Inc.

Address Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 11:30 A Day 8 Month 1 Year 1968

The above well was plugged as follows:

RTD 4310' 8 5/8 csg set at 274' cwc 210 sc. Cementing Material 50-50 Poz W/6% gel.  
Gunned pits, circulated heavy mud, set cementing plug at 750' and displaced 100 sc cem.  
thru drill pipe. Heavy mud to 300' set-cementing plug and displaced 25 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing  
Well Plugging Supervisor

DATE 1/11/68  
INV. NO. 7073-4