

15-135 20497-00-00

Form CP-3
Rev. 6-4-68

KANSAS

af STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1971
CONSERVATION DIVISION
Wichita, Kansas
10-22-1971

Operator's Full Name Okmar Oil Company & Walters Drilling Co.

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Elmore Well No. 1

Location C NW NW Sec. 16 Twp. 16 Rge. (E) (W) 21

County Ness Total Depth 4340'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 11 P Day 19 Month 10 Year 1971

The above well was plugged as follows:

RTD, 4340' 8 5/8 csg set at 382' cwc. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 360' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ken J. Massey
Well Plugging Supervisor

INVOICED

DATE 10/22/71

INV. NO. 4528-W