

15-135-20244-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1969
CONSERVATION DIVISION
Wichita, Kansas
05-02-1969

Operator's Full Name Chief Drilling Company, Inc.

Complete Address: Box 797 Great Bend, Kansas 67530

Elmore - Ryan

Lease Name Hearns - Well No. 1

Location App. 100' E of SE NE Sec. 16 Twp. 16 Rge. (E) (W) 21

County Ness Total Depth 4290

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: C. Tools

Address: License No.

Operation Completed: Hour 9P Day 30 Month 4 Year 1969

The Above well was plugged as follows:

RTD 4290' 8 5/8 csg set at 290' cwc 180 sk. Cmt. Mat. 50-50 poz cmt. W66% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 280' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to nase

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rex E. Mussey
Well Plugging Supervisor

DATE 5/2/69
INV. NO. 9705-W