

15-135-20030-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1967
05-25-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name McClure Oil Co. & Abercrombie Drlg. Inc.,

Complete Address: 1301 Wichita Plaza Wichita, Kansas

Lease Name Wierman Well No. 1

Location C NE SW Sec. 16 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4345

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Vaughan Drilling Co.

Address: Box 825 Great Bend, Kansas License No.

Operation Completed: Hour 7:30 P Day 23 Month 5 Year 1967

The Above well was plugged as follows:

RTD 4345' 8 5/8 csg set at 306' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 25 sc cem.

thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 5/26/67
INV. NO. 5285-4