

15-135-20916-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
01-06-1975
JAN 6 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Delg. Co
~~Dunne Gardner Petroleum, Inc.~~
Complete Address Suite 250, 200 W. Douglas, Wichita, Kansas
Lease Name Elmore RYAN Well No. 1
Location SW SW Sec. 15 Twp. 16 Rge. (E) (W) 21
County Ness Total Depth 4300'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 7:30 P Day 3 Month 1 Year 1975

The above well was plugged as follows:

RTD 4300' 8 5/8 csg set at 298' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 1/9/75
INV. NO. 616-W