

KANSAS

FORM CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

J. Lewis Breck  
Administrator  
245 North Water  
Wichita, Ks. 67202

API Number 15 -135-21,902<sup>00-00</sup> (of this well)

Operator's Full Name BEREN CORPORATION

Complete Address 970 FOURTH FINANCIAL, C.T.R. - WICHITA, KS. 67202

Lease Name RUBY Well No. #1

Location C-SE-SE Sec. 15 Twp. 16<sup>S</sup> Rge. 21 (E) (W) W

County NESS Total Depth 4290 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor STRATH DRILLING, CO.

Address 5619 - 8<sup>th</sup> ST. BOX 555 - GREAT BEND License No. KS.

Operation Completed: Hour 9:15<sup>AM</sup> Day 24 Month OCT Year 1980

The Above well was plugged as follows:

8 5/8" 365 FE SP. CUL. w/ 250 FE 6/40 Pozmix - 2% GEL. 3% CA-CL.

ORDERED 110 FE 50/50 Pozmix 6% GEL. + 8 5/8" PLUG. - ELV. 2326 K.B.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG. @ 740 FE w/ 70 FE CMT.

2<sup>ND</sup> PLUG. @ 360 FE w/ 25 FE CMT.

3<sup>RD</sup> PLUG. → SOLID BRIDGE HULLS + PLUG. @ 40 FE 100 w/ 10 FE CMT.

3 FE IN RAT HOLE.

2 FE IN MOUSE HOLE. BY SUN CMT.

I hereby certify that the above well was plugged as herein stated.

RECEIVED

Signed: Marion Schmidt  
Well Plugging Supervisor

OCT 29 1980  
10-29-1980  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 10-24-80  
DIV. NO. 4050-L