

15-135-20081-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1968

CONSERVATION DIVISION
Wichita, Kansas

07-08-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name O. A. Sutton

Complete Address: 800 Sutton Place Wichita, Kansas 67202

Lease Name Elmore Well No. 1

Location C NW SW Sec. 15 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4275'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Casing Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 12 N Day 5 Month 7 Year 1968

The Above well was plugged as follows:

Total Depth 4275' 8 5/8 csg set at 250' cwc.

5 1/2 csg set at 4276' cw 100 sc cement.

5 1/2 csg FBTD 4170' with top perf. at 4150'.

Pushed plug to 3800' and dumped 5 sc cement with dump bailer.

Recov. 2300' of 5 1/2 csg.

Pumped thru 8 5/8 plg container with 25 sc gel W/5 sc hulls, Plug and 140 sc 50-50

poz cement W/6% total gel. Max pres. 400 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 7/9/68
INV. NO. 8053-W