

15-135-20088-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1967
12-05-1967
CONSERVATION DIVISION
Wichita, Kansas

AM 5-6683

Operator's Full Name Walters Drlg. Co. & McClure Oil Co.

Complete Address: 400 Insurance Bldg. Wichita, Kansas

Lease Name Schwartzkopf Well No. 1

Location C NE NW Sec. 15 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4250

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Walters Drlg. Co.

Address: Wichita, Ks. License No. _____

Operation Completed: Hour 6:30 A Day 3 Month 12 Year 1967

The Above well was plugged as follows:

RTD 4250' 8 5/8 csg set at 247' cwc
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: R. W. Massey
Well Plugging Supervisor

INVOICED
DATE 12/5/67
INV. NO. 6844-W