

15-135-20058-00-00

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1968
CONSERVATION DIVISION
Wichita, Kansas

01-12-1968

Operator's Full Name Pickrell Drilling Company
Complete Address 705 Fourth Nat'l Bk. Bldg., Wichita, Ks.
Lease Name Harms-Kendall Well No. C-1
Location C SW SW Sec. 11 Twp. 16 Rge. 21 (E) (W) X
County Ness Total Depth 4266
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling Co.
Address Box 1082 Great Bend, Ks. License No. 623
Operation Completed: Hour 12:30 P Day 9 Month 1 Year 1968

The above well was plugged as follows:

Total Depth 4266' 8 5/8 csg set at 247' cwc 160 sc.
5 1/2 csg set at 4261' cw 100 sc cement.
PBDT 4225' and perf. (4125-28)
Filled with sand to 4100' and dumped 5 sc cement with dump bailer.
Recov. 3300' of 5 1/2 csg.
Pumped thru 8 5/8 plg container with 25 sc gel W/4 hulls, 120 sc cement, 5 sc gel,
plug and 15 sc cement and shutin with 300 lbs. pres.
Cement (0-50) gel (50-200) cement (200-680) Gel (680 to 3300)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russ Massey
Well Plugging Supervisor

DATE 1/12/68
INV. NO. 7082-W