

15-135-20498-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Harms Well No. 1

Location C NW SE Sec. 11 Twp. 16 Rge. (E) (W) 21

County Ness Total Depth 1838'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated Anhydrite Test

Plugging Contractor Strata Drilling

Address Wichita, Kansas License No.

Operation Completed: Hour 8 A Day 23 Month 10 Year 1971

The above well was plugged as follows:

RTD 1838' 8 5/8 csg set at 366' cwc 170 sk. Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 330' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Red T. Messing
Well Plugging Supervisor

INVOICED

DATE 11/2/71

INV. NO. 4569-44