

15-135-20735-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 1973
05-02-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name National Oil Company

Complete Address 550 O. W. Garvey Bldg., Wichita, Kansas

Lease Name Zeller Well No. 1

Location SE SW Sec. 5 Twp. 16 Rge. (E) (W) 21

County Ness Total Depth 4340'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor H-30 Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 7 P Day 26 Month 4 Year 1973

The above well was plugged as follows:

RTD 4340': 8 5/8 csg set at 252' cwc 175 sk. Cmt. Mat. 50-50 W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cem thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 5/2/73
INV. NO. 7318-W