

1080231

TO: STATE CORPORATION COMMISSION

11-25

API NUMBER 15-101-21,364-0001
NW SE SE SEC. 13, T 19 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HINEMAN WELL # 1 OWWO

TECHNICIAN'S PLUGGING REPORT COUNTY LANE 152.75

OPERATOR LICENSE # 30742 WELL TOTAL DEPTH 4700 FEET

OPERATOR: PALOMINO PETROLEUM PRODUCTION CSG: SIZE 5 1/2" @ 4699' WITH 200 SX

NAME AND ADDRESS 4924 SE 84TH ST SURFACE CASING: SIZE 8 5/8" @ 214' WITH 150 SX

ADDRESS NEWTON, KS 67114-8824

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DS&W WELL SERVICING LICENSE NUMBER 6901

ADDRESS PO BOX 231 CLAFLIN, KS 67525

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 25 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENT STRUBE

(COMPANY NAME) DS&W (PHONE) 316-587-3361

WERE: PERFS AT 4283-4348. ALT II COMPLETED 2000' TO 0' WITH 400 SX CEMENT

ALLIED PUMPED DOWN 5 1/2 250# HULLS WITH 50# HULLS MIXED IN 25 SX CEMENT, PUMPED 18 SX GEL

AND 195 SX CEMENT. MAXIMUM PSI PRESSURE AT 1500#. SHUT IN AT 1000#. PUMPED DOWN

8 5/8 x 5 1/2 ANNULAS AND ANNULAS FULL PRESSURED UP TO 500#.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 25 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT

ALLIED PUMPED DOWN 5 1/2 250# HULLS WITH 50# HULLS MIXED IN 25 SX CEMENT, PUMPED 18 SX GEL

AND 195 SX CEMENT. MAXIMUM PSI PRESSURE AT 1500#. SHUT IN AT 1000#. PUMPED DOWN

8 5/8 X 5 1/2 ANNULAS AND ANNULAS FULL. PRESSURED UP TO 500#.

RECEIVED
DEC 2 - 2-98
STATE CORPORATION COMMISSION
Wichita, Kansas
CONSERVATION DIVISION

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube (TECHNICIAN) FORM CP-2/3

DEC 04 1998
60413