

1 090086

6-10-15-101-21588-00-00

159

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-  
SW SW NW, SEC. 13, T. 19 S, R. 28 W/E  
2970 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30128  
Operator: Kenneth S. White  
Name & Address: 200 E. 1st, Suite 210  
Wichita, KS 67202

Lease Name Sleeper Well # 1  
County Lane 152.75  
Well Total Depth 4700 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie, RTD, Inc. License Number 30684  
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 10 Month: 6 Year: 19 01

Plugging proposal received from Tony Martin

(company name) Abercrombie, RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2110-40'

1st plug at 2150' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,  
3rd plug at 600' with 50 sx cement, 4th plug at 270' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:30 p.m. Day: 10 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1200' with 80 sx cement,  
3rd plug at 600' with 50 sx cement,  
4th plug at 270' with 50 sx cement,  
5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-14-91  
JUN 14 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 7-8-91

INV. NO. 32262

6-10

Signed (TECHNICIAN)