

1090284

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,119-0000
SW NW NE, SEC. 18, T 19 S, R 28 W XX

TECHNICIAN'S PLUGGING REPORT

4290 feet from N/S section line
2310 feet from W/E section line

Operator License # 5020

Lease Name Hineman Well # 1-18

Operator: Rine Exploration Company

County Lane 152.27

Name & Address 300 W. Douglas, Suite 645

Well Total Depth 4685 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 31st Month: January Year: 19 85

Plugging proposal received from Howard Cain

(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2130' with 50 sx cement

2nd plug at 1680' with 50 sx cement

3rd plug at 390' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole
with 10 sx cement

Plugging Proposal Received by R. Bartlett
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:01 am Day: 1 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement, 2nd plug at 1680' with 50

sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole

with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

FEB 07 1985

2-7-85

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Dowell
(if additional description is necessary, use BACK of this form.)

INVOICED (copy) observe this plugging.

Signed R. Bartlett
(TECHNICIAN)

DATE 2-14-85

INV. NO. 6978