

1 090373

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-21,430-0500

NE SW NW, SEC. 20, T 19 S, R 28 W/X

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30742

Lease Name Lenore Well # 1

Operator: Palomino Petroleum, Inc.

County Lane

Name & Address: 4924 SE 84th St.

Well Total Depth 4680 152.10 feet

Newton, KS 67114-8827

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Palomino Petroleum, Inc. License Number 30742

Address 4924 SE 84th St., Newton, KS 67114-8827

Company to plug at: Hour: 11 a.m. Day: 10 Month: 12 Year: 1993

Plugging proposal received from Steve Robben

(company name) Palomino Petroleum, Inc. (phone) 913-735-9405

was: 5 1/2" at 4677' w/550' sx cement, PBTD 4663'. Perfs at 4379-84, 4342-47', cemented w/350 sx

Upper stage  
1st plug hook onto 5 1/2" casing and pump in 2 sx hulls, 50 sx cement, 15 sx gel, and 160 sx cement.

Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 10 Month: 12 Year: 1993

ACTUAL PLUGGING REPORT 1st plug hooked onto 5 1/2" casing and pumped in 2 sx hulls, 50 sx cement, 15 sx gel, and 160 sx cement. Maximum pressure 1000 psi and shut in 200 psi.

Hooked onto backside, shut in pressure 300#.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form)

Signed \_\_\_\_\_ (TECHNICIAN)

INVOICED

DATE 12-30-93

INV. NO. 39604

RECEIVED  
STATE CORPORATION COMMISSION  
12-16-93  
DEC 16 1993  
CONSERVATION DIVISION CP-2  
Wichita, Kansas Rev. 01-