

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-101-20, 911-0000  
SE, Sec. 20, T 19 S, R 28 W/E  
1650 feet from N/S section line  
2210 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Hineman Well # 1

Operator: Chief Drilling Co. Inc  
Name &  
Address 905 Century Plaza  
Wichita KS  
67202

County Lane  
Well Total Depth 4693 feet 152.52  
Conductor Pipe: Size \_\_\_\_\_ feet \_\_\_\_\_  
Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita KS 67202

Company to plug at: Hour: 1:00pm Day: 12 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Harold Dinkle

(company name) Warrior Drilling Co (phone) \_\_\_\_\_

were: To fill hole w/heavy mud + spot cement through drill pipe  
1st plug @ 2130 w/50sx, 2nd plug @ 1620' w/50sx  
3rd plug @ 1020' w/50, 4th plug @ 360' w/40sx.  
5th plug @ 40' w/solid Bridge of bulls; wiper plug + 10sx  
cement, Circulate 15sx in the Rathole Using 60/40  
poz mix 2% gel 3% cc

Signed Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:45 pm Day: 12 Month: January Year: 1984

ACTUAL PLUGGING REPORT Filled hole w/heavy mud + spotted cement through drill pipe  
1st plug @ 2130' w/50sx, 2nd plug @ 1620 w/50sx w/50sx  
3rd plug @ 1020 w/50sx, 4th plug @ 360' w/40sx, 5th  
plug @ 40' w/solid Bridge plug w/ bulls - wiper plug  
+ 10sx, 6th plug circulate 15sx in the Rathole. Using  
60/40 poz mix 2% gel 3% cc filled hole between plugs

Remarks: Allied pumped the cement  
Bob Tarbutten gave plugging proposal

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 18 1984  
1-18-84  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1-20-84  
INV. NO 9199 W

Signed Richard W. Lacey  
(TECHNICIAN)