

1 040786

9-25

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,662-0000
NE SE NE, SEC. 20, T 19 S, R 28 W/E
1650 feet from NXX section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30269

Lease Name Toburen Well # 1

Operator: Argent Energy, Inc.

County Lane

Name & Address 110 S. Main, Ste. 810

Well Total Depth 4690 152.42 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: _____ Day: 24 Month: 9 Year: 19 93

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2124-54'

1st plug at 2154' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:15 a.m. Day: 25 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 650' with 50 sx cement,

4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this to

I (XXX) did not observe this plugging.

DATE: 10-7-93

WV. NO. 38890

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 10-6-93 OCT 06 1993

CONSERVATION DIVISION Wichita, Kansas