

To: 1 370338
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-21,662-0001

NE SE NE, SEC. 20, T 19 S, R 28

3630 feet from NXX section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

4-19

Operator License # 31283

Lease Name Warren Toburen Well # 1

Operator: Rheem Resources, Inc.

County Lane 143.65

Name: Rheem Resources, Inc.

Well Total Depth 4420 feet

Address 100 S. Main, Ste. 505

Conductor Pipe: Size _____ feet

Wichita, KS 67202-3738

Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 1:30 a.m. Day: 19 Month: 4 Year: 19 96

Plugging proposal received from Doug Hoffenstein

(company name) Murfin Drilling Co. (phone) 316-267-3241

Work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2150' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:30 a.m. Day: 19 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2150' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 650' with 50 sx cement, 4th plug at 300' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

(Check or) observe this plugging.

DATE APR 24 1996

Signed Kevin D Strube
(TECHNICIAN)

INV. NO. 45438

4-19

RECEIVED
KANSAS CORPORATION
APR 23 AM 07
4-23-96