

1 060078

6-8

149

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,589-0000

App. E/2 SE NE SEC. 24, T 19 S, R 28 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.  
Name & Address: 125 N. Market, Suite 1000  
Wichita, KS 67202

3300 feet from S section line

330 feet from E section line

Lease Name Methodist Church Well # 1

County Lane 151.45

Well Total Depth 4660 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor White & Ellis Drilling Inc. License Number 5420

Address 401 E. Douglas, Suite 500, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 8 Month: 6 Year: 19 91

Plugging proposal received from Judy

(company name) White & Ellis Drilling Inc. (phone) 316-263-1102

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2061-88'

1st plug at 2100' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 50 sx cement, 4th plug at 250' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 a.m. Day: 8 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 250' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

6-13-91 JUN 13 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 6-8-91

INV. NO. 32254