

1 090302

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,136-0000
SE NW SE, SEC. 24, T 19 S, R 28 W EX

1650 feet from N/S section line
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Haag Well # 1

Operator: National Cooperative Refinery Asso. County Lane
Name & Address P. O. Box 6
Great Bend, KS 67530

Well Total Depth 4705 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 11 Month: March Year: 19 85

Plugging proposal received from Bruce Fickel

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2040' with 50 sx cement

2nd plug at 1590' with 70 sx cement

3rd plug at 450' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:25 pm Day: 11 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement, 2nd plug at 1590' with 70 sx cement, 3rd plug at 450' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

MAR 15 1985
3-15-85
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied # 39269
(If additional description is necessary, use BACK of this form.)

I (~~did~~ / did not) observe this plugging.

Signed Robert B. Tarbutton
(TECHNICIAN)

3-18-85
7367

3-11