

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-073-01125-00-00
Spot: NWSEW Sec/Twnshp/Rge: 17-25S-9E
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HENDRICKSON C Well #: 1
County: GREENWOOD Total Vertical Depth: 2329 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	76		65 SX
PROD	5.5	2363		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2012 11:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: MATT OSBORN Company: _____ Phone: (620) 583-5527

Proposed Plugging Method: 50' cement plug @ 2148' 50' cement plug @ 900' 150' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 03/28/2012 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

perforated casing @ 900' & 150', ran tubing to 2148' pumped 20 sxs cement , pulled tubing to 900' pumped 20 sxs cement . Pulled tubing to 150' pumped 47 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2269	2281		
2204	2214		

RECEIVED

APR 4 2012 MH

KCC Chanute Dist. #3

RECEIVED
APR 11 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)