

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05300-00-00
Spot: NENWNE Sec/Twnshp/Rge: 34-11S-17W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: JOHANSEN Well #: 3
County: ELLIS Total Vertical Depth: 3542 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	238		150 SX
L1	5.5	3518		
PROD	7	3518		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/05/2012 11:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVE FUNK Company: QUALITY OIL WELL CEMENTING Phone: (785) 324-0643

Proposed Plugging Method:	Ordered - 525sacks 60/40 poz mix 4% gel; 500 # hulls. Emergency plug with rig over hole. Perforators perfed 2 shot holes @ 1650', 1215', 747', 200' Junk in hole
---------------------------	---

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/05/2012 5:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Professional Pulling Services RIH with tubing to 2812', Quality rigged to tubing & mixed & pumped 125sacks 60/40 poz mix with 300 # hulls mixed in.
Pulled tubing to 1650' Quality rigged to tubing & mixed & pumped 180 sacks with 200 # hulls mixed in. No circulation.
Pulled tubing to 1000' Quality rigged to tubing & mixed & pumped 185 sacks to circulate cement up 5.5" liner.
Pulled tubing rigged to 5.5" liner with a swedge & valve & pumped 35 sacks to circulate cement up 10" CSG.
Shut in 10" CSG.
Pressured 10" CSG & 5.5" liner with 100#PSI & 100# SIP.

Perfs:

Top	Bot	Thru	Comments
3518	3542		
3386	3390		
3336	3340		
3230	3236		

RECEIVED
APR 13 2012
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING CO.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

APR 09 2012

CM
4/27/12
Form CP-2/3