

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22551-00-00  
Spot: SWSENW Sec/Twnshp/Rge: 8-10S-23W  
2970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: DIETZ Well #: 2  
County: GRAHAM Total Vertical Depth: 4020 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3880		
SURF	8.625	224		228 SX
SURF	8.625	228		
PROD	5.5	4014		450 SX
PROD	5.5	4020		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2012 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: \_\_\_\_\_ Phone: (785) 421-2103

Proposed Plugging Method: 450 SXS 60/40 POZ 4% GEL 8 SXS GEL 450 # HULLS SHOOT PERFS 2050', 1150' 225'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2012 2:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RUN TUBING TO 3702' PUMP 8 SXS GEL FOLLOWED WITH 50 SXS CEMENT PULL TUBING TO 2215' PUMP 125 SXS CEMENT 200 # HULLS PULL TUBING TO 1139' PUMP 125 SXS CEMENT GOOD CIRCULATION OF CEMENT. TOP OFF CASING WITH 25 SXS CEMENT FULL. TIE ON BACK SIDE PUMP 10 SXS SHUT IN 300 PSI.

Perfs:

Top	Bot	Thru	Comments
3952	3956		
3914	3920		

RECEIVED  
APR 13 2012  
KCC WICHITA

Remarks: COSOLIDATED CEMENT CO TK # 33804

Plugged through: TBG

District: 04

Signed Marvin Mills  
(TECHNICIAN)

APR 10 2012

✓ 4/27/12 <sup>CM</sup>  
Form CP-2/3