

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20873-00-00
Spot: NESW Sec/Twnshp/Rge: 31-17S-34W
2100 feet from S Section Line, 1940 feet from W Section Line
Lease Name: NORTH SIX Well #: 1
County: SCOTT Total Vertical Depth: 5040 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	249		WITH 180 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/08/2012 11:30 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: LARRY HINDERLITER Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2490' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 04/08/2012 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2490' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP


District: 01

RECEIVED

APR 13 2012

KCC DODGE CITY

Signed



(TECHNICIAN)

RECEIVED

APR 17 2012

KCC WICHITA

Form CP-2/3

4/27/12
RAW