

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20869-00-00  
Spot: NESESESW Sec/Twnshp/Rge: 31-18S-34W  
560 feet from S Section Line, 2500 feet from W Section Line  
Lease Name: KRUSE-NOVAK Well #: 1-31  
County: SCOTT Total Vertical Depth: 5050 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	308		WITH 210 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2012 8:30 PM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 340' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE

Plugging Proposal Received By: DANIEL BERNASCONI WitnessType: NONE  
Date/Time Plugging Completed: 04/10/2012 10:30 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

1ST PLUG AT 2430' WITH 50 SX CMT. 2ND PLUG AT 1320' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 50 SX CMT. 4TH PLUG AT 340' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed

Daniel Bernasconi

(TECHNICIAN)

RECEIVED

APR 16 2012

KCC DODGE CITY

RECEIVED  
APR 18 2012  
4-18-12  
KCC WICHITA

Form CP-2/3

*Handwritten initials*