

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

**CANNOT INV. OPER. FOR THIS WELL AS PLUG DI. EXCEEDS 3 YR. CUTOFF.*
API Well Number: 15-167-05882-00-00
Spot: SWNENW Sec/Twnshp/Rge: 25-14S-15W
990 feet from N Section Line, 3630 feet from E Section Line
Lease Name: HARBAUGH J P A Well #: 9
County: RUSSELL Total Vertical Depth: 3169 feet

Operator License No.: 31250

Op Name: HUXMAN, RICHARD LEON DBA KSCO

Address: PO BOX 567
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	817		425 SX CMT
PROD	5.5	3163		150 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID FUNK

Company: QUALITY WELL SERVICE, INC.

Phone: (785) 483-3854

Proposed
Plugging
Method:

WELL WAS SQUEEZED in 1981. HOLE @ 333-361 CEMENTED WITH 125 SX Q.S. AND CIRCULATED UP 8-5/8.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/01/2004 3:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Backside full of cmt- squeezed @330'
Perf gun hit bridge @400'. Ran tubing to 500' and pulled back out.
Perforated @1450' and 780'
Ran tubing to 1400'
Pumped 60 sx cmt
Pulled tubing to 700'
Circulated w/80 sx cmt
POOH
Tied onto 4 1/2" casing and pumped 110 sx cmt
600 psi- Max 200 psi- SIP

Perfs:

Top	Bot	Thru	Comments
3163	3168	OH	

Remarks: ALLIED CEMENTING

Plugged through: TBG


RECEIVED

APR 19 2012

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

APR 16 2012