

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
March 2010

This Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Form KSONA-1, Certification of Compliance with the Kansas Surface Owner Notification Act,
MUST be submitted with this form.

OPERATOR: License #: 34381
Name: Urban Oil and Gas Group, LLC
Address 1: 1000 E. 14th St
Address 2: _____
City: Plano State: TX Zip: 75074 + _____
Contact Person: Robby Rockey
Phone: (972) 423-1199

API No. 15 - 173-20349 - 0200
If pre 1967, supply original completion date: _____
Spot Description: NW NW NW
NW NW NW Sec. 14 Twp. 26 S. R. 2 East West
565 4715 Feet from North South Line of Section
385 4895 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Sedgwick
Lease Name: Hamant Well #: B2

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8-5/8 Set at: 228' Cemented with: 200 Sacks
Production Casing Size: 5-1/2 Set at: 3161' Cemented with: unknown Sacks

List (ALL) Perforations and Bridge Plug Sets:

Well is open hole completion, previous operator dropped tubing and rods in hole. Top of fish located at 550'. Urban attempted to fish tubing 5/2011 but only retrieved 8' of rods.

Elevation: 1379 (G.L. / K.B.) T.D.: 3161 PBTD: _____ Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Cut off and remove 5-1/2" casing 50' above top of fish at 500'. Set 8-5/8" CIBP at 500' and spot 50' plug on top. Set 8-5/8" CIBP at 200' and cement to surface. Cut off wellhead below surface.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: Robby Rockey
Address: 1000 E. 14th St City: Plano State: TX Zip: 75074 + _____
Phone: (972) 423-1199

Plugging Contractor License #: _____ Name: _____
Address 1: _____ Address 2: _____
City: _____ State: _____ Zip: _____ + _____
Phone: (____) _____

Proposed Date of Plugging (if known): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/17/2012 Authorized Operator / Agent: _____
(Signature)

RECEIVED

APR 24 2012

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form KSONA-1
July 2010
Form Must Be Typed
Form must be Signed
All blanks must be Filled

**CERTIFICATION OF COMPLIANCE WITH THE
KANSAS SURFACE OWNER NOTIFICATION ACT**

This form must be submitted with all Forms C-1 (Notice of Intent to Drill); CB-1 (Cathodic Protection Borehole Intent); T-1 (Request for Change of Operator Transfer of Injection or Surface Pit Permit); and CP-1 (Well Plugging Application). Any such form submitted without an accompanying Form KSONA-1 will be returned.

Select the corresponding form being filed: C-1 (Intent) CB-1 (Cathodic Protection Borehole Intent) T-1 (Transfer) CP-1 (Plugging Application)

OPERATOR: License # 34381
Name: Urban Oil and Gas Group, LLC
Address 1: 1000 E. 14th St
Address 2: _____
City: Plano State: TX Zip: 75074 + _____
Contact Person: Robby Rockey
Phone: (972) 423-1199 Fax: (972) 423-5533
Email Address: rrokey@urbanoilandgas.com

Well Location:
NVN\NV\ Sec. 14 Twp. 26 S. R. 2 East West
County: Sedgwick
Lease Name: Hamant Well #: B2

If filing a Form T-1 for multiple wells on a lease, enter the legal description of the lease below:

Surface Owner Information:

Name: Alvin & Helena Hamant Trust
Address 1: 7305 E 30th Circle
Address 2: _____
City: Wichita State: KS Zip: 67226 + _____

When filing a Form T-1 involving multiple surface owners, attach an additional sheet listing all of the information to the left for each surface owner. Surface owner information can be found in the records of the register of deeds for the county, and in the real estate property tax records of the county treasurer.

If this form is being submitted with a Form C-1 (Intent) or CB-1 (Cathodic Protection Borehole Intent), you must supply the surface owners and the KCC with a plat showing the predicted locations of lease roads, tank batteries, pipelines, and electrical lines. The locations shown on the plat are preliminary non-binding estimates. The locations may be entered on the Form C-1 plat, Form CB-1 plat, or a separate plat may be submitted.

Select one of the following:


I certify that, pursuant to the Kansas Surface Owner Notice Act (House Bill 2032), I have provided the following to the surface owner(s) of the land upon which the subject well is or will be located: 1) a copy of the Form C-1, Form CB-1, Form T-1, or Form CP-1 that I am filing in connection with this form; 2) if the form being filed is a Form C-1 or Form CB-1, the plat(s) required by this form; and 3) my operator name, address, phone number, fax, and email address.

I have not provided this information to the surface owner(s). I acknowledge that, because I have not provided this information, the KCC will be required to send this information to the surface owner(s). To mitigate the additional cost of the KCC performing this task, I acknowledge that I am being charged a \$30.00 handling fee, payable to the KCC, which is enclosed with this form.

If choosing the second option, submit payment of the \$30.00 handling fee with this form. If the fee is not received with this form, the KSONA-1 form and the associated Form C-1, Form CB-1, Form T-1, or Form CP-1 will be returned.

I hereby certify that the statements made herein are true and correct to the best of my knowledge and belief.

Date: 4/17/2012 Signature of Operator or Agent: _____ Title: Engineering Manager



RECEIVED

APR 24 2012



April 17, 2012

Kansas Corporation Commission
District #2
3450 N. Rock Road, Building 600, Suite 601
Wichita, KS 67226
Attn: Dan Fox

Re: Urban Oil and Gas Temporarily Abandoned Wells

Mr. Fox:

In response to your letter dated March 5, 2012 regarding Urban Oil and Gas Group, LLC's temporarily abandoned wells, please find attached the following:

- For API Well # 15-173-20419-00-00, Hamant B3: Please find attached the submitted form ACO-1. This well was reactivated as a Kansas City producer in May of 2011.
- For API Well # 15-173-20349-00-00, Hamant B2: Please find attached the completed form CP-1 and KSONA-1. Urban attempted to fish the dropped rods and tubing out of this well in May of 2011. After three days of fishing, we were only able to retrieve one 8' section of pony rod. Please find attached a copy of the workover report for that job. We will begin plugging operations on this well immediately after we receive KCC approval.

Please let me know if I can provide any more information. Thank you for your time and assistance in this matter.

Sincerely,

A handwritten signature in black ink, appearing to read 'Robby Rockey', written over a white background.

Robby Rockey
Engineering Manager
Urban Oil and Gas Group, LLC
Office: 972-423-1199
Cell: 972-951-0997
rrockey@urbanoilandgas.com

1000 E. 14TH | PLANO, TX 75074
MAIN 972.423.1199 | FAX 972.423.5533
URBANOILANDGAS.COM

RECEIVED
APR 24 2012
KCC WICHITA

DAILY ACTIVITY AND WORKOVER REPORT

Urban Oil & Gas			Report No: 1		
Well Name: Hamant B2			Date: 5-24-11		
County: Sedgewick			Field: Hamant		
Daily Cost: 3573			Cum. Cost: 3573		
Supervisor: D Franks		Job Type: Fish Tbg	TD	PBTD Fish @ 544'	Perfs
Date and Report					
<p>Held Safety mtg. 0#-CP.RU M&S WS.PU, TIH w/4.5" Rotary shoe, 3-jts 4.5" washpipe, X-overs, 14-jts 2 7/8" tbg. Tag Fish @ 544'. RU Power Swivel. Break circ w/21 bbl SW. Burn over fish for 4 hrs, made 4'. PU above fish, circ clean. SD for storms.</p>					

RECEIVED
APR 24 2012
KCC WICHITA

DAILY ACTIVITY AND WORKOVER REPORT

Urban Oil & Gas			Report No: 2		
Well Name:Hamant B2			Date: 5-25-11		
County: Sedgewick			Field: Hamant		
Daily Cost: 4800			Cum.Cost: 8373		
Supervisor: D Franks	Job Type: Fish Tbg	TD	PBTD Fish @ 544'	Perfs	
Date and Report					
<p>Held Safety mtg.0#-WHP.Break circ w/2 bbl SW.Tag 548'.Burn over fish appr 3.5 hrs,made 2.5'.Circ & POOH.Rec 2 7/8" x 8' pup jt w/pony rod wrapped around it.Did not find anything inside pup jt.RIH w/4.5" LIB.POOH,had 2' Pony rod stuck in face of block.TIH w/same block.POOH,showed impression of rod body lying across face on LIB. TIH w/another 4.5" Rotary shoe,3-jts WP,x-overs,14-jts tbg.RU Swl,break circ /w/1 bbl.Burn over fish appr 3.5 hrs, Made 6".Shoe was torqued up quite a bit,drilling on very hard fish.</p>					

RECEIVED
 APR 24 2012
 KCC WICHITA

DAILY ACTIVITY AND WORKOVER REPORT

Urban Oil & Gas			Report No: 3		
Well Name: Hamant B2			Date: 5-26-11		
County: Sedgewick			Field: Hamant		
Daily Cost: 2383			Cum. Cost: 10756		
Supervisor: D Franks		Job Type: Fish Tbg	TD	PBTD Fish @ 550'	Perfs
Date and Report					
<p>Held Safety mtg. 0#-WHP. Break circ w/1 bbl SW. Mill over fish appr 2.5 hrs, made no hole. Circ & POOH. Shoe was cracked, broken. Decided to quit fishing job. Load out fishing tools. RDMO all equipment.</p>					

RECEIVED
APR 24 2012
KCC WICHITA



Mark Sievers, Chairman
Ward Loyd, Commissioner
Thomas E. Wright, Commissioner

Corporation Commission

Sam Brownback, Governor

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

URBAN OIL AND GAS GROUP LLC
1000 E 14TH ST
PLANO, TX 75074

April 27, 2012

Re: HAMANT #2-B
API 15-173-20349-00-00
14-26S-2E, 4715 FSL 4895 FEL
SEDGWICK COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after October 24, 2012. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000