

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19866-00-00
Spot: SWSWNWSE Sec/Twnshp/Rge: 17-35S-10E
1276 feet from S Section Line, 2543 feet from E Section Line
Lease Name: BYBEE Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 1400 feet

Operator License No.: 32687 •

Op Name: MYERS DRILLING AND EXPLORATION

Address: 415 SHERMAN ST.
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		50		
PROD	3.5	990		400 SX

Well Type: SWD

UIC Docket No: D24477.0

Date/Time to Plug: 01/19/2012 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: RONALD MYERS

Company:

Phone: (620) 725-3338

Proposed Plugging Method: RUN 1" TO TD. GEL HOLE. SPOT 10 SX OF CEMENT ON BOTTOM. PULL UP TO 550'. CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed 01/20/2012 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 960' gelled hole and spotted 6 sack plug. Pulled up to 750' and spotted 6 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 42 sacks of cement were used to plug this well.

RECEIVED

APR 3 2012 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]

(TECHNICIAN)

RECEIVED

APR 05 2012 Form CP-2/3

KCC WICHITA