

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-24832-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 17-35S-10E
1116 feet from S Section Line, 1862 feet from E Section Line
Lease Name: BYBEE Well #: 3A
County: CHAUTAUQUA Total Vertical Depth: 1499 feet

Operator License No.: 32687
Op Name: MYERS DRILLING AND EXPLORATIO
Address: 415 SHERMAN ST.
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	42		25 SX
PROD	4.5	1499		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2012 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: RONALD MYERS Company: _____ Phone: (620) 725-3338

Proposed Plugging Method: RUN 1" TO TD. GEL HOLE. SPOT 10 SX OF CEMENT ON BOTTOM. PULL UP TO 1200'. SPOT 5 SX OF CEMENT. PULL UP TO 550'. CEMENT TO SURFACE.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 01/23/2012 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1500' gelled hole and spotted 10 sack plug. Pulled up to 1200' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 70 sacks of cement were used to plug this well.

RECEIVED
APR 8 2012
DAS
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

RECEIVED

Form CP-2/3

APR 05 2012

KCC WICHITA