

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10587-00-00
Spot: NESW Sec/Twnshp/Rge: 16-33S-41W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 27-4
County: MORTON Total Vertical Depth: 5450 feet

Operator License No.: 32659
Op Name: PHOENIX PETROCORP, INC.
Address: 6401 S CUSTER RD, STE 130
MCKINNEY, TX 75070

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1489		WITH 650 SX CMT
PROD	4.5	5130	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: OBSTRUCTION AT 2700'. ATTEMPT TO GET BY & SET CIBP @ 4975'. PLUG AT 1520' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 03/20/2012 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

OBSTRUCTION AT 2700'. UNABLE TO GET BY OBSTRUCTION IN CASING AT 2341' WITH CIBP. RIH W/TBG & STACKED OUT AT 2374'. POOH W/TBG, RIH WITH TBG & PACKER TO 1584', PUMPED 75 SX CMT & 100# HULLS DISPLACING TO 2200'. SI. WOC. TESTED CASING, HELD OK. PERFORATED CASING @ 1530'. RIH W/TBG & PACKER TO 1150'. PUMPED 80 SX CMT. DISPLACED TO 1300'. SDON. TAGGED TOC @ 1279'. PERFORATED CASING @ 550'. PUMPED 150 SX CMT DOWN CASING CIRCULATING CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5042	5046		
5032	5036		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

KCC WICHITA

RECEIVED

MAR 29 2012

KCC DODGE CITY

Form CP-2/3

RECEIVED
APR 05 2012

AWZ