

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00556-00-00  
Spot: SESW Sec/Twnshp/Rge: 18-35S-41W  
660 feet from S Section Line, 1980 feet from W Section Line  
Lease Name: NORTHWEST FLATS UNIT Well #: 3B-1  
County: MORTON Total Vertical Depth: 4901 feet

Operator License No.: 32659  
Op Name: PHOENIX PETROCORP, INC.  
Address: 6401 S CUSTER RD, STE 130  
MCKINNEY, TX 75070

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1545		WITH 700 SX CMT
PROD	4.5	4900	0	WITH 210 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/15/2012 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: RIH W/TBG & PACKER TO 3700' & PUMP 100# HULLS & 75 SX CMT. PRESSURE TEST CASING. IF HOLDER PERF @ 1450' & PUMP 80 SX CMT. PERFORATE @ 450' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE  
Date/Time Plugging Completed: 03/15/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

**\*\*TOC @ 4200' PER TEMP SURVEY. CASING RESTRICTION @ 3995'.\*\*** RIH W/TBG & PACKER TO 3700'. PUMPED 75 SX CMT & 100# HULLS. SHUT DOWN & WAIT ON CMT. PRESSURE TESTED CASING TO 500#. HELD OK. PERFORATED CASING AT 1450' & PUMPED 80 SX CMT. PERFORATED CASING AT 450'. CIRCULATED CMT TO SURFACE WITH 200 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4840	4850		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
APR 05 2012  
KCC WICHITA

RECEIVED  
MAR 21 2012  
KCC DODGE CITY