

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-101-22351-00-00  
Spot: SWNESWSE Sec/Twnshp/Rge: 22-18S-27W  
810 feet from S Section Line, 1735 feet from E Section Line  
Lease Name: MAGGIE ROBBINS, LLC Well #: 1  
County: LANE Total Vertical Depth: 4627 feet

Operator License No.: 5046  
Op Name: RAYMOND OIL COMPANY, INC.  
Address: PO BOX 48788  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	269		WITH 175 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/26/2012 10:30 AM  
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.  
Proposal Rcvd. from: DAVE YOTT Company: L. D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: 1ST PLUG AT 2010' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 03/26/2012 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2010' WITH 50 SX CMT. 2ND PLUG AT 1140' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

RECEIVED  
MAR 30 2012  
KCC DODGE CITY

Signed

*Kenny M. Sullivan*  
(TECHNICIAN)

KCC WICHITA

RECEIVED  
APR 05 2012

*RAY*