

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20758-00-00
Spot: NENW Sec/Twnshp/Rge: 6-35S-26W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease Name: EDIGER Well #: 2-6
County: MEADE Total Vertical Depth: 6400 feet

Operator License No.: 8060
Op Name: ZENERGY, INC.
Address: 6100 S YALE STE 1700
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4550		WITH 2 SX CMT
SURF	8.625	1375		WITH 750 SX CMT
COND	20	135		WITH 10 SX CMT
PROD	5.5	6400	0	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/02/2012 10:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: KEITH HILL Company: ZENERGY INC. Phone: (918) 485-6400

Proposed Plugging Method: SET CIBP @ 4600' WITH 2 SX CMT. PERFORATE @ 140' & CIRCULATE CMT TO SURFACE UP 8 5/8".
MINIMUM OF 450 SX CMT ON LOCATION. COMPANY CHOSE NOT TO PULL PIPE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2012 2:37 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

SET CIBP @ 4550' WITH 2 SX CMT. PERFORATED AT 1400'. ESTABLISHED CIRCULATION WITH 27 BBL FRESH WATER. CIRCULATED CMT TO SURFACE WITH 320 SX CMT. HOLE STAYED FULL.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

RECEIVED

APR 05 2012

District: 01

RECEIVED

APR - 3 2012

KCC DODGE CITY

Signed



(TECHNICIAN)

KCC WICHITA

19007