

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20770-00-02
Spot: SESWNE Sec/Twnshp/Rge: 14-35S-12W
322 feet from S Section Line, 1734 feet from E Section Line
Lease Name: GOTTSCH-PETERMANN Well #: 1
County: BARBER Total Vertical Depth: 1000 feet

Operator License No.: 6006
Op Name: MOLZ OIL COMPANY
Address: 19159 SW CLAIRMONT
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	305		WITH 225 SX CMT
PROD	4.5	600	0	WITH 225 SX CMT

Well Type: SWD UIC Docket No: D21337.0 Date/Time to Plug: 03/29/2012 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 03/30/2012 12:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

PUMPED 100 SX COMMON CEMENT WITH 600# HULLS @ 502' THROUGH TBG.
PULLED TBG. PUMPED 15 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. BLEW HOLE
IN 8 5/8". SDON. 3/30/12: RAN 1" TBG TO 126' DOWN 8 5/8" X 4 1/2" ANNULUS.
PUMPED 75 SX CMT CIRCULATING SURFACE. RAN 2 3/8" TBG TO 155'. PUMPED 15
SX CMT CIRCULATING TO SURFACE. PULLED TBG & TOPPED OFF WITH 5 SX
CMT.

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

APR 05 2012

Form CP-2/3

KCC WICHITA

4/19/12

RECEIVED

APR - 3 2012

KCC DODGE CITY