

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22484-00-03  
Spot: NESENE Sec/Twnshp/Rge: 7-6S-21W  
1650 feet from N Section Line, 330 feet from E Section Line  
Lease Name: VOSS Well #: 4  
County: GRAHAM Total Vertical Depth: 3730 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3685		
SURF	8.625	256		175 SX
PROD	4.5	3728		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2012 12:00 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Rcvd. from: TOMMY ATKINS Company: PLAINS, INC Phone: (785) 216-0155

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
200# HULLS

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2012 2:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

RUN TUBING TO 2916' PUMP 150 SXS CEMENT. PULL TUBING TO 1500' PUMP 45 SXS CEMENT GOOD CIRCULATION OF CEMENT. PULL TUBING OUT OF HOLE TIE ONTO CASING SQUEEZE WITH 35 SXS CEMENT SHUT IN AT 775 PSI. TIE ON BACK SIDE SQUEEZE WITH 10 SXS SHUT IN AT 200 PSI.

Perfs:


Top	Bot	Thru	Comments
3693	3695		SPF
3599	3602		SPF
3588	3592		SPF
3482	3485		SPF
3451	3602		SPF
3376	3380		SPF

Remarks: ALLIED CEMENT CO TK # 40948

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

APR 03 2012

RECEIVED Form CP-2/3

APR 06 2012 4/19/12

KCC WICHITA