

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02401-00-00
Spot: SESENE Sec/Twnshp/Rge: 6-12S-17W
2944 feet from S Section Line, 412 feet from E Section Line
Lease Name: SHUTTS Well #: 1
County: ELLIS Total Vertical Depth: 3647 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1372		
PROD	5.5	3646		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2012 8:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE Phone: (620) 655-4494

Proposed Plugging Method: Ordered - 680 sacks 60/40 poz mix 4 % gel; 500 # hulls
CIBP @ 3300'
CSG leaks

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2012 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perforators perfed 2 shot holes @ 1850' & 1350'
Alliance Well Service RIH with tubing to 3205', Quality rigged to tubing & mixed & pumped 150 sacks with 300 # hulls mixed in.
Pulled tubing to 1850', Quality rigged to tubing & mixed & pumped 185 sacks with 200 # hulls mixed into circulate cement up 5.5" CSG.
Pulled tubing rigged to 5.5" CSG with a swedge & pumped 255 sacks to circulate cement up 8.625" CSG. Shut in 8.625" CSG & pumped to pressure. No shut in pressure head leaked off.

Perfs:

Top	Bot	Thru	Comments
3646	3667		ARBUCKLE (OPEN)

RECEIVED
APR 06 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICES (#31925) TICKET #

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

MAR 26 2012

Form CP-2/3

✓ 4/19/12