

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21555-00-00
Spot: SWSENW Sec/Twnshp/Rge: 20-7S-17W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KRILEY F Well #: 1
County: ROOKS Total Vertical Depth: 3305 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1145		400SX
SURF	8.625	1146		400 SX
PROD	5.5	3276		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/02/2012 12:45 PM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: BRYAN HESS Company: HESS OIL CO. Phone: (620) 241-4640

Proposed Plugging Method: Ordered 450 sacks 60/40 poz 4 % gel; 500 # hulls; 10 sacks gel.
Well has been sqzd.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/02/2012 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perfed @ 1100'
Kelso RIH with tubing to 3200.' Copeland rigged to tubing & mixed & pumped 10 sacks gel followed by 50 sacks 60/40 poz with 200 # hulls mixed in.
Pulled tubing to 1850' Copeland rigged to tubing & mixed & pumped 205 sacks 60/40 poz with 300 # hulls mixed into circulate cement up 5.5" CSG.
Pulled tubing rigged to 5.5" CSG with a swedge & pumped 25 sacks to pressure, blew a small hole in head no SIP.
8.625" CSG was full of cement.

Perfs:

Top	Bot	Thru	Comments
3276	3305		ARBUCKLE

Remarks: COPELAND CEMENTING CO. TICKET # 39314

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

APR 03 2012

RECEIVED

APR 06 2012

Form CP-2/3

4/19/12

KCC WICHITA