

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-06882-00-00
Spot: NESESW Sec/Twnshp/Rge: 14-15S-18W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GRAF Well #: 2
County: ELLIS Total Vertical Depth: 3570 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1139		450 SX
PROD	5.5	3557		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2012 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RICK POPP Company: CASTELLI EXPLORATION INC. Phone: (620) 786-5508

Proposed Plugging Method: Ordered - 750 sacks 60/40 poz mix 4 % gel; 11sacks gel; 500 # hulls
CIBP @ 3380' & 3410'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2012 3:10 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed @ 1100'
Express Well Service RIH with tubing to 3276' Quality rigged to tubing & mixed & pumped 11 sacks gel followed by 75 sacks 60/40 poz mix with 300 # hulls mixed in.
Express pulled tubing to 1650', Quality rigged to tubing & mixed & pumped 675 sacks with 200# hulls mixed into circulate cement up 5.5" CSG & up 8.6250" CSG. Shut in both CSG & pumped to pressure with 200 # PSI & 200 # SIP.

Perfs:

Top	Bot	Thru	Comments
3557	3570		ARBUCKLE- OH
3390	3393		KC
3259	3262		KC
2398	3304		KC

Remarks: QUALITY OIL WELL CEMENTING CO. TICKET # 306

Plugged through: TBG

RECEIVED

APR 06 2012

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

MAR 27 2012

Form CP-2/3

✓ 4/19/12